



Microbial population dynamics in constructed wetlands: Review of recent advancements for wastewater treatment

Rajitha J. Rajan^{1†}, J. S. Sudarsan^{2†}, S. Nithiyantham³

¹Department of Civil and Environmental Engineering, SRMIST, Kanchipuram Dt., Kattankulathur - 603 203, Tamil Nadu, India

²National Institute of Construction Management and Research (NICMAR), Balewadi, Pune, 411045, India.

³Post Graduate and Research Department of Physics, (Ultrasonic / NDT and Bio-Physics Divisions), Thiru.Vi.Kalyanasundaram Govt Arts & Science College, Thiruvavur, Tamilnadu 610003, India

ABSTRACT

Constructed wetlands are improvised man-made systems, designed for adopting the principle of natural wetlands for purifying wastewater – the elixir of life. They are used widely as a cost-effective and energy-efficient solution for treating greywater generated from different tertiary treatment sources. It provides an elaborate platform for research activities in an attempt to recycle earth's natural resources. Among the several organic impurities removal mechanisms existing in constructed wetland systems, the earth's active microbial population plays a vital role. This review deals with the recent advancements in constructed wetland systems from a microbiological perspective to (effect/ devise/ formulate) chemical and physical treatment for water impurities. It focuses on microbial diversity studies in constructed wetlands, influence of wetland media on microbial diversity and wetland performance, role of specific microbes in water reuse, removal of trace elements, some heavy metals and antibiotics in constructed wetlands. The impurities removal processes in constructed wetlands is achieved by combined interactive systems such as selected plant species, nature of substrate used for microbial diversity and several biogeochemical effected reaction cycles in wetland systems. Therefore, the correlation studies that have been conducted by earlier researchers in microbial diversity in wetlands are addressed herewith.

Keywords: Constructed wetlands, Denaturing Gradient Gel Electrophoresis (PCR-DGGE), Phytoremediation, Polymerase chain reaction

1. Introduction

Wetlands for water pollution control/remedy in use of wastewater for more than many decades. Many researchers give detailed information of the developments of describe the field, over time, engineering design, process and the control over the process. The scarcity of freshwater resources to meet the increasing demands of water usage and dwindling available resources are pressing problems encountered at a global level. Recovery alternatives such as wastewater treatment, aquifer recharge, rainwater harvesting, etc. are commonly adopted to deal with this situation to conserve water resources [1-5]. Mother Earth / Nature have her own ways of treating wastewater in which wetlands plays a dominant role. Wetlands are one of the natural methods of treating and preserving water resources all through the year in which water covers the soil surface for specific time duration and then percolates into the ground.

Wetlands are hence critical to groundwater recharge. Removal process involved in water treatment in treatment wetland (TW) includes number of many physiological; plant related and microbial related one [5-9].

The main role of constructed wetland is the land designed for vegetation and to treat wastewater. The main issue of constructed wetland requires large land area. 'The researchers may also defined wetland is the receiving water pollution, through design, period on a time on polishing water'. They also classifies TW systems on the basis of vegetation and hydrology, with subsurface systems as horizontal flow and vertical flow, and the hybrid systems having the contribution of both horizontal and vertical flow. Worldwide various types of flows systems existing depend on their suitability, availability and the maintenance. I.e., in America and Australia free water surface flow, rather Europe and their neighboring countries designed the subsurface flow. In general free water surface flow for secondary water treatment, whereas the subsurface flow



This is an Open Access article distributed under the terms of the Creative Commons Attribution Non-Commercial License (<http://creativecommons.org/licenses/by-nc/3.0/>) which permits unrestricted non-commercial use, distribution, and reproduction in any medium, provided the original work is properly cited.

Copyright © 2019 Korean Society of Environmental Engineers

Received March 31, 2018 Accepted August 7, 2018

† Corresponding author

Email: rajithajrajan@gmail.com, sudarsanjss@yahoo.com

Tel: +91-9003078348

ORCID: 0000-0001-6802-4541 (J. S. Sudarsan)

for tertiary water treatment [10-15]. At some point at equilibrium of attachment and detachment can occur allowing for steady state operation with no bio-clogging. Several important benefits are provided by wetlands; they maintain the diversity of the ecosystem which assists in the treatment of polluted water, by storing, purifying and recycling water resources in leaves, shoots and roots of wetland plants. They control water erosion by reducing storm and flooding damages; they also serve as a wildlife habitat, help sustain growth and maintain the natural equilibrium [16-20].

2. Constructed Wetlands

2.1. General

By adopting the principles of many natural wetlands, man-made/artificial wetlands are selectively designed and purposefully created in an attempt to obtain a fast growing simulated ecosystem using holistic engineered technology treatment to achieve better water quality. Constructed commercial wetlands are serving as an efficient method for brackish water recovery wastewater treatment and control of pollutants for decades. They are simulated water treatment systems that incorporate suitable vegetation and substrate, in addition to the use of a wide variety of microbial flora which play a crucial role in controlling pollution [4-6]. Comparative studies of constructed wetlands with other existing conventional methods have shown that treatment efficiency of horizontal subsurface flow wetland system is comparable (> 75% in total suspended solids) to conventional technologies in water treatment like rotating biological contactor and packed bed filters. Significant reduction in the construction cost and energy requirements makes Constructed Wetlands (CWs) a suitable alternative in wastewater treatment [6-7]. There is sufficient evidence to show that in addition to the treatment of municipal, industrial and agricultural wastewater. Urban storm water and landfill leachate can also be effectively treated by constructed wetlands with considerable reduction in Biological Oxygen Demand (BOD) and Chemical Oxygen Demand (COD) [8]. Additionally, the consistent behavior of constructed wetlands to intermittent operations and adverse conditions like flooding and drought makes it an alternative mitigation strategy with tertiary cycles that makes it a suitable option for organic wastewater treatment [9, 10].

2.2. Types of Wetlands

There are two types of constructed wetlands, namely surface flow wetlands and subsurface flow wetlands. Surface flow wetlands are very similar to natural wetlands and the wastewater flow over the substrate is not very deep. Subsurface flow wetlands are further classified into Vertical Flow (VF) (Fig. 1) and Horizontal Flow (HF) (Fig. 2) systems. Both have proved to be more effective than the surface systems [11-13]. A combination of VF and HF systems are also used which are known as hybrid wetlands (Fig. 3).

2.3. Wetland Plants

Wetland plants come under the category of macrophytes which includes four types namely emergent macrophytes, floating-leaved macrophytes, submerged macrophytes and freely floating




Fig. 1. Vertical flow-constructed wetland.




Fig. 2. Horizontal flow-constructed wetland.




Fig. 3. Hybrid flow-constructed wetland.

macrophytes. *Phragmites*, *Typha*, *Scirpus*, *Phalaris arundinacea*, and *Iris* are the common species of macrophytes that grow in wetlands [14-16]. The choice of plants has a bearing on the process efficiency. Some plants like *Cirpus grossus* have sustainable living biomass above the soil including stem, stump, branches, bark, seeds and foliage which increases its effectiveness but some others (e.g., *Typha angustifolia*) need to be replaced periodically for better performance [17].

The most important removal mechanism occurring in constructed wetlands is filtration. In addition several microbial-mediated processes, chemical networks, volatilization, sedimentation, sorption, photo-degradation, plant uptake, transpiration flux etc. also contribute to increasing the efficiency of the process either singularly or as a combination of two or more processes [18-19].

2.4. Wastewater Pollutants

Nitrogen in combined form is one of the principal pollutants present in wastewater; it exists in both organic and inorganic forms. The organic forms of nitrogen include amino acids, urea, uric acids, purines and pyrimidines, while free NH_3 , ammonium salts and nitrogen gas (Nitrogen is not a polluting compound) are the forms of inorganic nitrogen [20-24]. Nitrogen content is reduced through a series of treatment pathways such as ammonification, nitrification and denitrification, plant absorption uptake as nitrates, biomass assimilation, nitrate reduction, ammonia volatilization, adsorption, Anammox and Canon processes [25-29]. Several wastewater pollutants and their effects are listed in Table 1. From the table many

Table 1. Common Man-made Wastewater Pollutants and Their Effects [20-33]

SI No	Category	Name of pollutant	Effects
1	Organic pollutants	Nitrogen (Present as ammonia and organic nitrogen)	Presence of algal blooms in water, increase in the amount of chlorine, increasing risk of cancer, stimulation of harmful microbes like <i>Pfiesteria</i> which may lead to eye and respiratory irritation, headache, gastrointestinal complaints and methaemoglobinemia (blue-baby disease) in infants.
2		Phosphorus (Exists in the form of soluble orthophosphate? TSP is insoluble in water ion, organically-bound phosphate, or other phosphorus/oxygen forms)	
3	Hydrocarbons	Petroleum hydrocarbons	Significant damage to body organs (liver and kidney) and body functions, cause reproductive cytotoxicity and childhood cancers.
4	Heavy metals	Zinc	Cause stomach cramps, skin irritations, vomiting, nausea, anemia, damaged pancreas, disturbed protein metabolism, arteriosclerosis, respiratory disorders, danger to infants and unborn and increase in water acidity.
5		Lead	Kidney damage, interrupt hemoglobin synthesis and anemia.
6		Mercury	Toxic to aquatic organisms.
7		Cadmium	Interact with calcium metabolism in animals. In fish, causes larval mortality and temporary reduction in growth.
8		Chromium	Fish are more susceptible to infection. A high concentration of chromium is also known to cause damage in the tissues of several invertebrates, such as snails and worms.
9	Microorganisms	Harmful bacteria	Water-related diseases.
10		Viruses	Viral infections.
11		Protozoans	Leishmaniasis, Amoebiasis, Diarrhoea, Trichomoniasis, Tripanosomiasis, Lambliasis, Toxoplasmosis and Malaria.
13	Emerging Pollutants	Pharmaceutical products (antibiotics)	Slow development of aquatic organisms, increased masculinization of different fishes affecting their reproductive rates.
14	(Persistent Organic Pollutants)	Polychlorobiphenyls (PCBs)- A family of 209 chlorinated aromatic compounds	Act as endocrine disruptors.
15		Phthalates (plastics)	Low-molecular-weight phthalates improve motor skills in boys, high-molecular-weight phthalates lower orientation and alertness in girls, risk of endometriosis, early sexual maturation in girls, contribute to the risk of diabetes, lung disorders and disruption of other normal body functions.
16		Polycyclic aromatic hydrocarbons (PAHs)	PAHs may have short-term as well as long-term effects on the normal functioning of the body. Can cause embryotoxic, genotoxic, immunotoxic effects.
17		Bisphenol A (BPA)	Affect puberty and ovulation, lead to infertility, contribute to insulin resistance and therefore Type-2 diabetes, coronary artery heart disease, affect the developing brain during gestation, increase the risk of breast, prostate and other cancers.

of pollutants are very harmful to human community like kidney failure, causes of cancer, gastrointestinal diseases, reproductive system, diabetic, irritation in respiratory organs and eye and even its affects the infants.

So, the need for removal of pollutants is the major issue for researchers' reasonable and possible way. Wastewater BOD & COD, Pollutants are generally removed either aerobically or anaerobically by complex oxidation/methanation processes aided by diverse microorganisms of oxygen or sulphur loving bacteria (associated with

plant roots and sediments) [34]. An aerobic organism or aerobe is an organism that can survive and grow in an oxygenated environment. The atmospheric oxygen penetrates into the deeper layers of the substrate with the help of plant roots and creates an aerobic region in the close vicinity of roots. This zone is dominated by Methanotrophs, *Nitrosomonas* and *Pseudomonas aeruginosa* spp. which are responsible for the aerobic degradation of pollutants. Anaerobic regions are created away from the aerobic regions and are dominated by methanogenic and sulfur reducing bacteria. The

Table 2. List of Microbes with Efficiency

Sl No	Microorganisms studied	Treatment efficiency (% removal)	Wastewater studied	Type of Wetland	Reference
1	Total coliform, <i>Escherichia coli</i> (<i>E. coli</i>) and Helminth eggs	90%	Domestic wastewater	Hybrid systems (train with vertical and horizontal systems)	[102]
2	Fecal coliforms and total coliforms	99%	Septic wastewater effluent	Pilot-scale combined CW system	[103]
3	<i>Salmonella</i> , fecal coliforms and <i>E. coli</i>	96, 98 and 99%, respectively	Swine wastewater	Two-cell field-scale surface flow constructed wetland	[104]
4	Fecal coliforms and enterococci, <i>Salmonella</i> , <i>Giardia</i> cysts, <i>Cryptosporidium</i> oocysts	> 99%, 93-96%, 88% and 69%, respectively	Domestic wastewater	Horizontal flow constructed wetland	[105]
5	<i>E. coli</i> , <i>Salmonella</i> and helminth eggs	99.5% for <i>E. coli</i> , <i>Salmonella</i> and helminth eggs - 100% in all samples	Domestic wastewater	Horizontal subsurface flow constructed wetland	[106]
6	Coliphage, total coliforms, fecal coliforms, <i>Giardia</i> and <i>Cryptosporidium</i>	<i>Giardia</i> and <i>Cryptosporidium</i> (duckweed pond at 98 and 89%), coliphage, total and fecal coliforms SSF wetland (95, 99, and 98 percent, respectively)	Secondary unchlorinated wastewater	Three types: duckweed-covered pond, a multi-species subsurface flow (SSF) and a multi-species surface flow (SF) wetland were studied	[107]

anaerobic degradation is a two-step process in which the first step is fermentation and the second step is called methanogenesis [35-37].

The hydraulic retention time (HRT) also plays a pivotal role in specific pollutant removal. Studies have proved that suitable adoption of HRT results (Anaerobic behaves differently for proteins, carbs and fats in food – please check) in better removal efficiencies. For instance fecal coliform and N-removal efficiencies can be increased by increasing the HRT, while considerable P removal can be achieved with longer HRT probably greater than 15 d [38-39]. Thus a series of factors as discussed above along with modified wetland designs and active management are to be considered for the efficient working of CWs in order to improve the effluent water quality [40-42].

The presence of bacteria, fungi, and algae are abundant in wetlands and they enhance the organic pollutant removal in subsurface flow wetland systems. Microorganisms play a key role in the biogeochemical cycles of wetland systems and each species of microbes has its own contribution towards the treatment of wastewater from different sources having varying pollutant loads. The clear understanding of effluent interactions with the wetland systems and the characteristics of the improved water thus obtained after treatment will pave the way for customized design of CW units depending on the nature of the feed it is receiving [43-45].

This review is focused on the microbiological advances in constructed wetlands area. The understanding about the role of microorganisms is important because the efficiency achieved as a result of the treatment is due the combined interaction between the plants in the wetland, wetland media, type of wastewater used and the pollutants associated with it as well as the characteristics such pH, temperature, humidity and other environmental conditions.

This paper therefore addresses several perspectives that contribute to the microbiological efficiency of constructed wetlands. It includes the microbial diversity studies in constructed wetlands, the correlation of microorganisms in several other phenomena occurring in the system, the contribution of different substrates to the microbial diversity and richness and the contribution of microorganisms in ensuring treatment efficiency. Compare the process of anaerobic is efficient than aerobic. And the list of microbes is given in Table 2.

3. Recent Microbiological and Molecular Biological Studies

3.1. Microbial Diversity Studies in Constructed Wetlands

Microorganisms are of critical importance to the symbiotic health of earth's inhabitants and play a vital role in the removal/conversion of pollutants in constructed wetland systems [46]. The microbial fauna is present in the soil matrix, which is further divided into aerobic and anaerobic zones. The aerobic zones are rich in microbial diversity which assists in metal oxidation (bacteria fixes inorganics by reacting only with its organic content) while the latter are rich in sulphate-reducing bacteria [47-48]. The concentration of ammoniacal nitrogen, nitrate, nitrogen and carbonaceous materials contributes to the abundance of microorganisms in the wetland system. The decay products of plant litter also play a part in the growth of microorganisms in the surface layer [49]. Numerous studies have been undertaken/done for determining the role of various parameters influencing the microbial efficiency of contaminant removal in constructed wetlands. Any research on basic living

organisms, such as indigenous microorganisms demands a vast arena of traditional techniques ranging from isolation, culturing and identification to modern techniques of gene sequencing, PCR-DGGE and a lot more besides [12, 50].

Studies on microbial diversity of natural and constructed wetlands are accomplished by characterization of the soil bacteria community structure and composition [51]. This can be done by several microbiological techniques, one of which is pyrosequencing of 16S ribosomal DNA [52]. Pyrosequencing of 16S ribosomal DNA from soil samples collected from different locations of constructed wetlands when compared to the results of samples from natural wetlands, revealed that natural wetlands harbor a wider variety of microorganisms than those in CWs. Studies have proved that the diversity of bacterial populations living inside plant tissues are shaped as a result of several physiochemical and biological processes that occur in wetlands [53]. The amount of oxygen present at different periods as well as the organic load contributes to the bacterial diversity of constructed wetland systems [12]. The availability of nutrients and their characteristics also influences microbial diversity in CWs. Oxygen regulates nutrient biogeochemistry in constructed wetlands and the improved sediment quality is due to the presence of deep rooted macrophytes [54].

The microbial diversity is found to be a function of configuration and design of the CWs. The performance and microbial diversity of two pilot-scale multi-stage sub-surface flow constructed wetland systems and the results indicated a linkage between microbial community, treatment performance and design of the CWs; an increased bacterial diversity was observed in the last stage of multi-stage CWs. This study also pointed to a link between nutrient removal and community composition [55].

The prevailing pattern of water flow over a given time, specifically, the duration and timing at which surface water is present in the CW unit is one important factor that determines the structure of the bacterial communities in the wetland complex soils and sediments [56]. The bacterial community structure and the specific bacterial consortia within wetlands determine the denitrification potential. The extent of denitrification occurring in CWs is linked to bacterial communities [43, 57-58]. The study, conducted on riparian plant species, revealed that biological diversity is strongly related to steep environmental gradients in hydrology and soil redox status [59]. To understand the mechanism behind the source of microbial organisms from the CW, Ibekwe carried out / undertook characterization of microbial composition of soil samples from two constructed wetlands treating dairy wash-water using PCR-DGGE. The results from this study revealed that the source of bacterial communities present in soil samples was from the gastrointestinal tracts of animals. It also showed higher percentage of *Nitrosospira*-like sequences and *Nitrosomonas*-like sequences which confirmed/ showed/ revealed that wetland systems are highly dependent upon the microbial activities and diversities for optimal wastewater treatment and the nature of wastewater to be treated [44].

Another recent study suggested that each plant favors growth of specific microbial communities and plant diversity helps to harbor different species of microorganisms which respond differently to factors such as nutrient availability, contaminant loads, specific plant species and combinations selected thus increasing microbial based wastewater treatment capacity [60-61].

Contrary to the (above-mentioned research findings/observations stated earlier), certain studies reported that plants do not have any (significant impact) on the structure of the microbial communities [62].

3.2. Correlation Studies in Wetlands

The contamination removal procedure in CWs is rarely achieved by individual processes (BOD reduction only needs photosynthesis oxygen from cyanobacteria), but by the combined interaction of plant species present in the system, nature of substrate used in the system, microbial diversity and several biogeochemical cycles of wetland systems. Each component contributes at its own level to the overall efficiency of the wetland system and hence correlation studies play an important role in understanding the ecological and biophysical processes in wetlands. For example, studies have proved that in the filtration process, the filter materials used and the resident plants exert considerable effect on the establishment of microbial community in wetland systems [63]. As stated earlier, plant diversity helps to harbor a huge variety of microbial species which means that the microbial activities in planted wetlands are usually more than that in unplanted wetlands. Depending upon the different C:N:P ratios provided by wastewater from various sources, the plant growth is affected and in due time produces a more stable ecosystem within it [64]. River water purification methods involving CWs, the microorganisms present in the soil, especially the species and their number, the enzyme activities of the soil and the rate of pollutant removal maintained significant correlations [65]. Studies on fumigation extraction and ecoplate techniques showed that plant diversity increases the plant biomass production and is well correlated with the size and structure of soil microbial community patterns in constructed wetlands [66].

Experiments conducted in two-stage CWs treating tannery wastewater, planted with *Typha latifolia* and *Phragmites australis* in expanded clay aggregates for 31 months and analyzed the diversity of bacterial communities by enumeration techniques and DGGE. They came to the conclusion that there is no clear relation between the sample collection time, hydraulic loading applied and the bacterial diversity [22, 67].

3.3. Influence of Wetland Media

Different unconventional wetland media are used for treating different types of wastewaters and their removal efficiencies are monitored in various studies. They eventually accelerate nutrient removal and foster microbial diversity.


The removal efficiencies of different substrates vary; the maximum removal efficiency of a component in question can be attributed to one substrate rather than the other one, which will offer the same for another component (Fig. 4 and 5). These differences can be explained in part by the fact that each substrate is different from the other with reference to physical and chemical characteristics [68-69]. The type of substrate and the presence of suitable plant species assist in pollutant removal. It promotes the richness and diversity of suitable species of microbes that can contribute to better treatment efficiency [70]. Substances like carbohydrates are degraded in the portions of the substrates where dense roots are present. Microorganisms harbored by the substrates also serve as a predefined measure used to track the treatment efficiency

of CW units [71]. Studies showed that there is a dominance of *Nitrosomonas* species in the vicinity of plant roots, enhancing the nitrogen removal when compared to the non-vegetated residues [72]. Also, when compared to substrate, higher bacterial diversity is found in the rhizosphere region.

A comparative study of various substrates in removing phosphorus (P) showed that the choice of adsorbing substrate greatly influences the lifetime of constructed wetlands [73]. Wetlands can be effectively used in the removal of non-biodegradable pollutants. The important factors to be considered while selecting the substrate materials are high sorption capacity, efficiency, easy availability and economical factor/aspect [74-76]. Some of the widely used substrates in CW and their applications are stated.

Maerl (calcified seaweed) is a highly potential constructed wetland substrate, with a proven reported phosphorus removal rate of 98% [77]. Compost was used as a substrate for treating wastewater in vertical flow wetlands from refineries where total suspended solids, COD, BOD and heavy metals were removed with significant removal percentages [78]. The use of coal slag bed to treat domestic wastewater showed 60% removal efficiency for carbonaceous matters, 50% removal of ammonia nitrogen, 40% for phosphorus and 80% efficiency in removing total suspended solids [79]. Gravel and Zeolite were also experimented as bedding material and the average removal efficiencies for ammonia nitrogen, COD, Phosphorus and Fe(III) were compared for units operating in horizontal and vertical modes. Ammonia nitrogen, Fe(III) and Phosphorus showed more efficiency in vertical flow CW units while the COD removal was high in horizontal flow CW units [80].

The substrates such as blast furnace artificial slag, coal burn artificial slag, and mid-sized sand artificial slag were also analyzed for the removal of total P (TP), total N (TN) and ammonium N. The results indicated that the percentage removal of TN was high in coal burn artificial slag while the others were high in blast furnace artificial slag [81]. Complete total oxidized nitrogen removal was observed in rice husk media [82]. High efficiency of ammonia removal and highest total nitrogen removal efficiency of 59.5% was observed in CW systems in which lightweight aggregates of fly ash were used as substrate [17].



* The removal efficiency of rice husk was monitored for different HLR and the results showed that systems with longer HRT had maximum efficiency.

Fig. 4. Comparison of removal efficiency of $\text{NH}_4\text{-N}$ in different Bed materials.




Fig. 5. Comparison of removal efficiency of TN in different Bed materials.

3.4. Role of Microbes in Water Reuse, Removal of Trace Elements, Heavy Metals and Antibiotics

Research studies on the reuse of water after CW treatment requires knowledge of the origin of (septage and sewage) wastewater as well as the type of indicator microorganisms such as total coliforms, fecal coliforms and *E. coli* [83-86].

Treated wastewater is widely used for watering, landscaping and aquifer recharging purposes. It is therefore recommended that cost-effective and energy-efficient techniques be adopted for wastewater reuse [87] without precipitating chemicals. Experimental evidences suggest that constructed wetlands play an efficient role in the removal of wastewater containing xenobiotic compounds, illicit drugs, transformation products, antibiotics, etc. [88-89].

It was reported that the use of halotolerant microorganisms improves the efficiency of treatment [90-91]. Halotolerant varieties of vegetation and their associated sediments improve the exposure of air in the system and provide better conditions for the growth of aerobic halotolerant microorganisms, which in turn improves the removal efficiencies of the CW unit [92-93]. The study of presence of pathogens and the effectiveness of connected bacteria is necessary to ensure the reuse of treated water [94]. On the other hand, some studies show that increase in microbial activity need not always/necessarily contribute to the water quality after treatment [54].

Heavy metals, one of the highly toxic environmental contaminants are produced by a variety of industries and are treated with conventional methods like reverse osmosis (RO) and nanofiltration (NF) technologies [95]. Constructed wetlands planted with *Phragmites australis* have proved to be efficient in the removal of heavy metals such as arsenic and zinc through principal processes such as sorption, precipitation and co-precipitation the system showed highest microbial diversity and richness with a dominating Proteobacteria [96-97]. The degradation of antibiotics is also a feature which is accomplished by microbial pathways, regulated by the presence or absence of plants, the flow type, temperature, artificial aeration redox potential and most importantly the CW design characteristics, though the removal efficiency is proved to be a little low in cold climatic conditions [98-99]. Studies showed 90% removal of trace elements such as Cd, Cr, Pb, As, Zn and BOD from sewage with higher treatment efficiency in summer than in winter [100-101].

4. Conclusions

Recommendations Regarding the Sustainable Application of Constructed Wetlands

Constructed wetlands offer an economic, self-maintained and cost-effective alternative for the conventional treatment of different types of wastewater. This review is focused mainly on the microbial prospects which form the basis of the removal mechanisms in constructed wetland systems such as ammonification, nitrification, denitrification, plant uptake, biomass assimilation, etc.

Moreover, microbial efficiency of constructed wetlands is also required to be studied to decide the prospects of further treatment of wastewater before its release to the environment. Not much literature is available regarding the percentage removal of pathogenic microorganisms existing in wastewater from different sources and such areas of research need to be encouraged for the optimization of the microbial parameters which may aid in the sustainable application of constructed wetlands.

The availability of nutrients and the mode of utilization, oxygen solubility/ conditions, organic matter load, design and configuration of the CWs, type of water regime and plant diversity are the other parameters that need to be addressed. Influence of wetland media is another important arena, as the type of substrate along with the presence of suitable plant species is crucial in determining the bacterial composition which is ultimately responsible for the removal efficiency of the system. Though there are certain experimental results existing in these areas, many basic contradictions are also present. These exceptions and contradictions of treatment technologies need to be analyzed carefully and the specific conditions required for maximum output have to be optimized before the design, construction and execution of every constructed wetland project.

References

1. Adrados B, Sanchez O, Arias CA, et al. Microbial communities from different types of natural wastewater treatment systems: Vertical and horizontal flow constructed wetlands and biofilters. *Water Res.* 2014;55:304-312.
2. Qingqing C, Wang H, Chen X, Wang R, Liu J. Composition and distribution of microbial communities in natural river wetlands and corresponding constructed wetlands. *Ecol. Eng.* 2017;98:40-48.
3. Ligi T, Oopkaup K, Truu M, et al. Characterization of bacterial communities in soil and sediment of a created riverine wetland complex using high-throughput 16S rRNA amplicon sequencing. *Ecol. Eng.* 2014;72:56-66.
4. Ahn C, Gillevet PM, Sikaroodi M. Molecular characterization of microbial communities in treatment microcosm wetlands as influenced by macrophytes and phosphorus loading. *Ecol. Indic.* 2007;7:852-863.
5. Akpor OB, Otohinoyi DA, Olaolu TD, Aderiye BI. Pollutants in wastewater effluents: Impacts and remediation processes. *Int. J. Environ. Res. Earth Sci.* 2014;3:50-59.
6. Andersson J, Kallner Bastviken S, Tonderski KS. Free water surface wetlands for wastewater treatment in Sweden nitrogen and phosphorus removal. *Water Sci. Technol.* 2005 ;51:39-46.
7. Ansola G, Arroyo P, de Miera LE. Characterisation of the soil bacterial community structure and composition of natural and constructed wetlands. *Sci. Total Environ.* 2014;473:63-71.
8. Armstrong J, Armstrong W. *Phragmites Australis* – A preliminary study of soil oxidizing sites and internal gas-transport pathways. *New Phytol.* 1998;108:373-382.
9. Arroyo P, Ansola G, de Miera LE. Effects of substrate, vegetation and flow on arsenic and zinc removal efficiency and microbial diversity in constructed wetlands. *Ecol. Eng.* 2013;51:95-103.
10. Aslam MM, Malik M, Baig MA, Qazi IA, Iqbal J. Treatment performances of compost-based and gravel-based vertical flow wetlands operated identically for refinery wastewater treatment in Pakistan. *Ecol. Eng.* 2007;30:34-42.
11. Babatunde AO, Miranda-Caso Luengo R, Imtiaz M, Zhao YQ, Meijer WG. Performance assessment and microbial diversity of two pilot scale multi-stage sub-surface flow constructed wetland systems. *J. Environ. Sci.* 2016;46:38-46.
12. Bahr M, Crump BC, Klepac-Ceraj V, Teske A, Sogin ML, Hobbie JE. Molecular characterization of sulfate-reducing bacteria in a New England salt marsh. *Environ. Microbiol.* 2005;7:1175-1185.
13. Baptista JD, Davenport RJ, Donnelly T, Curtis TP. The microbial diversity of laboratory-scale wetlands appears to be randomly assembled. *Water Res.* 2008;42:3182-3190.
14. Bastviken SK, Eriksson PG, Martins I, Neto JM, Leonardsson L, Tonderski K. Potential nitrification and denitrification on different surfaces in a constructed treatment wetland. *J. Environ. Qual.* 2003;32:2414-2420.
15. Behrends L, Houke L, Bailey E, Jansen P, Brown D. Reciprocating constructed wetlands for treating industrial, municipal and agricultural wastewater. *Water Sci. Technol.* 2001;44:399-406.
16. Bertino A. Study on one-stage partial nitrification-Anammox process in moving bed biofilm reactors: A sustainable nitrogen removal. TRITA LWR Degree Project, Royal Institute of Technology (KTH) Stockholm, Sweden; 2010.
17. Bia1owiec A, Janczukowicz W, Randerson PF. Nitrogen removal from wastewater in vertical flow constructed wetlands containing LWA/gravel layers and reed vegetation. *Ecol. Eng.* 2011;37:897-902.
18. Morvannou A, MarcChoubert J, Vanclooster M, Molle P. Modeling nitrogen removal in a vertical flow constructed wetland treating directly domestic wastewater. *Ecol. Eng.* 2014;70:379-386.
19. Bitton G. Wastewater microbiology. John Wiley & Sons; 2005 May 27.
20. Bojcevska H, Tonderski K. Impact of loads, season and plant species on the performance of a tropical constructed wetland polishing effluent from sugar factory stabilization ponds. *Ecol. Eng.* 2007;29:66-76.
21. Button M, Rodriguez M, Brisson J, Weber KP. Use of two spatially separated plant species alters microbial community function in horizontal subsurface flow constructed wetlands. *Ecol. Eng.* 2016;92:18-27.
22. Calheiros CS, Duque AF, Moura A, et al. Changes in the bacterial community structure in two-stage constructed wetlands with different plants for industrial wastewater treatment. *Bioresour.*

- Technol.* 2009;100:3228-3235.
23. Calheiros CS, Duque AF, Moura A, et al. Substrate effect on bacterial communities from constructed wetlands planted with *Typha latifolia* treating industrial wastewater. *Ecol. Eng.* 2009;35:744-753.
 24. Calheiros CS, Teixeira A, Pires C, et al. Bacterial community dynamics in horizontal flow constructed wetlands with different plants for high salinity industrial wastewater polishing. *Water Res.* 2010;44:5032-5038.
 25. Truu J, Nurk K, Juhanson J, Mander U. Variation of microbiological parameters within planted soil filter for domestic wastewater treatment. *J. Environ. Sci. Health Part A* 2005;40:1191-1200.
 26. Calheiros CS, Ferreira V, Magalhaes R, Teixeira P, Castro PM. Presence of microbial pathogens and genetic diversity of *Listeria monocytogenes* in a constructed wetland system. *Ecol. Eng.* 2017;102:344-351.
 27. Calheiros CS, Pereira SI, Brix H, Rangel AO, Castro PM. Assessment of culturable bacterial endophytic communities colonizing *Canna flaccida* inhabiting a wastewater treatment constructed wetland. *Ecol. Eng.* 2017;98:418-426.
 28. Calheiros CS, Rangel AO, Castro PML. Evaluation of different substrates to support the growth of *Typha latifolia* in constructed wetlands treating tannery wastewater over long-term operation. *Bioresour. Technol.* 2008;99:6866-6877.
 29. Calheiros CS, Rangel AO, Castro PML. The effects of tannery wastewater on the development of different plant species and chromium accumulation in *Phragmites australis*. *Arch. Environ. Contam. Toxicol.* 2008;55:404-414.
 30. Calheiros CS, Rangel AO, Castro PM. Constructed wetlands for tannery wastewater treatment in Portugal: Ten years of experience. *Int. J. Phytoremediat.* 2014;16:859-870.
 31. Carballeira T, Ruiz I, Soto M. Aerobic and anaerobic biodegradability of accumulated solids in horizontal subsurface flow constructed wetlands. *Int. Biodeterior. Biodegr.* 2017;119:396-404.
 32. Carvalho PN, Basto MCP, Almeida CMR. Potential of *Phragmites australis* for the removal of veterinary pharmaceuticals from aquatic media. *Bioresour. Technol.* 2012;116:497-501.
 33. Caselles-Osorio A, Villafañe P, Caballero V, Manzano Y. Efficiency of mesocosm-scale constructed wetland systems for treatment of sanitary wastewater under tropical conditions. *Water Air Soil Pollut.* 2011;220:161-171.
 34. Chan SY, Tsang YF, Chua H, Sin SN, Cui LH. Performance study of vegetated sequencing batch coal slag bed treating domestic wastewater in suburban area. *Bioresour. Technol.* 2008;99:3774-3781.
 35. Pedescoll A, Corzo A, Álvarez E, García J, Puigagut J. The effect of primary treatment and flow regime on clogging development in horizontal subsurface flow constructed wetlands: An experimental evaluation. *Water Res.* 2011;45:3579-3589.
 36. Chung AK, Wu Y, Tam NY, Wong MH. Nitrogen and phosphate mass balance in a sub-surface flow constructed wetland for treating municipal wastewater. *Ecol. Eng.* 2008;32:81-89.
 37. Cui L, Ouyang Y, Lou Q, et al. Removal of nutrients from wastewater with *Canna indica* L. under different vertical-flow constructed wetland conditions. *Ecol. Eng.* 2010;36:1083-1088.
 38. Dan A, Yang Y, Dai YN, Chen CX, Wang SY, Tao R. Removal and factors influencing removal of sulfonamides and trimethoprim from domestic sewage in constructed wetlands. *Bioresour. Technol.* 2013;146:363-370.
 39. Dordio AV, Carvalho AJ. Organic xenobiotics removal in constructed wetlands, with emphasis on the importance of the support matrix. *J. Hazard. Mater.* 2013;252:272-292.
 40. Dwire KA, Kauffman JB, Baham JE. Plant species distribution in relation to water-table depth and soil redox potential in montane riparian meadows. *Wetlands* 2006;26:131-146.
 41. Erler DV, Tait D, Eyre BD, Bingham M. Observations of nitrogen and phosphorus biogeochemistry in a surface flow constructed wetland. *Sci. Total Environ.* 2011;409:5359-5367.
 42. Fatta-Kassinos D, Kalavrouziotis IK, Koukoulakis PH, Vasquez MI. The risks associated with wastewater reuse and xenobiotics in the agroecological environment. *Sci. Total Environ.* 2011;409:3555-3563.
 43. Fountoulakis MS, Terzakis S, Chatzinotas A, Brix H, Kalogerakis N, Manios T. Pilot-scale comparison of constructed wetlands operated under high hydraulic loading rates and attached bio-film reactors for domestic wastewater treatment. *Sci. Total Environ.* 2009;407:2996-3003.
 44. Garcia J, Rousseau DPL, Morato J, Lesage E, Matamoros V, Bayona JM. Contaminant removal process in subsurface-flow constructed wetlands: A review. *Crit. Rev. Environ. Sci. Technol.* 2010;40:561-661.
 45. Gray S, Kinross J, Read P, Marland A. The nutrient assimilative capacity of maerl as a substrate in constructed wetland systems for waste treatment. *Water Res.* 2000;34:2183-2190.
 46. Haandel A, Lubbe J. Handbook of biological waste water treatment. Design and optimization of activated sludge systems. Leidschendam, The Netherlands: Quist Publishing; 2007.
 47. Hijosa-Valsero M, Fink G, Schlüsener MP, et al. Removal of antibiotics from urban wastewater by constructed wetland optimization. *Chemosphere* 2011;83:713-719.
 48. Huang L, Gao X, Liu M, Du G, Guo J, Ntakirutimana T. Correlation among soil microorganisms, soil enzyme activities, and removal rates of pollutants in three constructed wetlands purifying micro-polluted river water. *Ecol. Eng.* 2012;46:98-106.
 49. Ibekwe AM, Grieve CM, Lyon SR. Characterization of microbial communities and composition in constructed dairy wetland wastewater effluent. *Appl. Environ. Microbiol.* 2003;69:5060-5069.
 50. Ansola G, Arroyo P, Sáenz de Miera LE. Characterization of the soil bacterial community structure and composition of natural and constructed wetlands. *Sci. Total Environ.* 2014;473-474:63-71.
 51. Jia W, Zhang J, Wu J, Xie H, Zhang B. Effect of intermittent operation on contaminant removal and plant growth in vertical flow constructed wetlands: A microcosm experiment. *Desalination* 2010;262:202-208.
 52. Jinadasa KB, Tanaka N, Sasikala S, Werellagama DR, Mowjood MI, Ng WJ. Impact of harvesting on constructed wetlands performance – A comparison between *Scirpus grossus* and *Typha angustifolia*. *J. Environ. Sci. Health Part A* 2008;43:664-671.
 53. Kadlec RH. Comparison of free water and horizontal subsurface treatment wetlands. *Ecol. Eng.* 2009;35:159-174.
 54. Karajić M, Lapanje A, Razingger J, Zrimec A, Vrhovšek D. The effect of the application of halotolerant microorganisms on the efficiency of a pilot-scale constructed wetland for saline waste-

- water treatment. *J. Serb. Chem. Soc.* 2010;75:129-142.
55. Karajić M, Razinger J, Zrimec A, Vrhovšcaron D, Katz SA. Microbial activity in a pilot-scale, subsurface flow, sand-gravel constructed wetland inoculated with halotolerant microorganisms. *Afr. J. Biotechnol.* 2012;11:15020-15029.
 56. Khatoun H, Yusoff F, Banerjee S, Shariff M, Bujang JS. Formation of periphyton biofilm and subsequent biofouling on different substrates in nutrient enriched brackishwater shrimp ponds. *Aquaculture* 2007;273:470-477.
 57. Kjellin J, Hallin S, Worman A. Spatial variations in denitrification activity in wetland sediments explained by hydrology and denitrifying community structure. *Water Res.* 2007;41:4710-4720.
 58. Lee C, Fletcher T, Sun G. Nitrogen removal in constructed wetland systems. *Eng. Life Sci.* 2009;9:11e22.
 59. Leverenz H, Haunschild K, Hopes G, Tchobanoglous G, Darby JL. Anoxic treatment wetlands for denitrification. *Ecol. Eng.* 2010;36:1544-1551.
 60. Liang W, Wu ZB, Cheng SP, Zhou QH, Hu HY. Roles of substrate microorganisms and urease activities in wastewater purification in a constructed wetland system. *Ecol. Eng.* 2003;21:191-195.
 61. Ligi T, Oopkaup K, Truu M, et al. Characterization of bacterial communities in soil and sediment of a created riverine wetland complex using high-throughput 16S rRNA amplicon sequencing. *Ecol. Eng.* 2014;72:56-66.
 62. Huang W, Chen X, Jiang X, Zheng B. Characterization of sediment bacterial communities in plain lakes with different trophic statuses. *Microbiologyopen* 2017;6:e00503.
 63. Lizama K, Fletcher TD, Sun G. Removal processes for arsenic in constructed wetlands. *Chemosphere* 2011;84:1032-1043.
 64. Masi F, Conte G, Lepri L, Martellini T, Del Bubba M, Florence I. Endocrine disrupting chemicals (EDCs) and pathogens removal in an hybrid CW system for a tourist facility wastewater treatment and reuse. In: Proc. of the 9th IWA International Conference on Wetland Systems for Water Pollution Control, Avignon, France 2004;2:461-468.
 65. Matheson FE, Sukias JP. Nitrate removal processes in a constructed wetland treating drainage from dairy pasture. *Ecol. Eng.* 2010;36:1260-1265.
 66. Mina IA, Costa M, Matos A, Calheiros CS, Castro PM. Polishing domestic wastewater on a subsurface flow constructed wetland: Organic matter removal and microbial monitoring. *Int. J. Phytoremediat.* 2011;13:947-958.
 67. Nahlik AM, Mitsch WJ. Tropical treatment wetlands dominated by free-floating macrophytes for water quality improvement in Costa Rica. *Ecol. Eng.* 2006;28:246-257.
 68. Ouellet-Plamondon C, Chazarenc F, Comeau Y, Brisson J. Artificial aeration to increase pollutant removal efficiency of constructed wetlands in cold climate. *Ecol. Eng.* 2006;27:258-264.
 69. Patra AK, Abbadie L, Clays-Josserand A, et al. Effects of management regime and plant species on the enzyme activity and genetic structure of N-fixing, denitrifying, and nitrifying bacterial communities in grassland soils. *Environ. Microbiol.* 2006;8:1005-1016.
 70. Picek T, Cizková H, Dusek J. Greenhouse gas emissions from a constructed wetland plants as important sources of carbon. *Ecol. Eng.* 2007;31:98-106.
 71. Prathap MG, Sudarsan JS, Mukhopadhyay M, Reymond DJ, Nithiyantham S. Constructed wetland – An easy and cost-effective alternative for the treatment of leachate. *Int. J. Energ. Technol. Policy* 2015;11:371-379.
 72. Puigagut J, Caselles-Osorio A, Vaello N, García J. Fractionation, biodegradability and particle-size distribution of organic matter in horizontal subsurface-flow constructed wetlands. In: Vymazal J, ed. Wastewater treatment, plant dynamics and management in constructed and natural wetlands. 2008. p. 289-297.
 73. Qdais HA, Moussa H. Removal of heavy metals from wastewater by membrane processes: A comparative study. *Desalination* 2004;164:105-110.
 74. Rai UN, Upadhyay AK, Singh NK, Dwivedi S, Tripathi RD. Seasonal applicability of horizontal sub-surface flow constructed wetland for trace elements and nutrient removal from urban wastes to conserve Ganga River water quality at Haridwar, India. *Ecol. Eng.* 2015;81:115-122.
 75. Ruiz-Rueda O, Hallin S, Baneras L. Structure and function of denitrifying and nitrifying bacterial communities in relation to the plant species in a constructed wetland. *FEMS Microbiol. Ecol.* 2008;67:308-319.
 76. Saeed T, Sun G. A review on nitrogen and organics removal mechanisms in subsurface flow constructed wetlands: Dependency on environmental parameters, operating conditions and supporting media. *J. Environ. Manage.* 2012;112:429-448.
 77. Salomo S, Munch C, Roske I. Evaluation of the metabolic diversity of microbial communities in four different filter layers of a constructed wetland with vertical flow by Biolog™ analysis. *Water Res.* 2009;43:4569-4578.
 78. Sharma S, Aneja MK, Mayer J, Munch JC, Schloter M. Characterization of bacterial community structure in rhizosphere soil of grain legumes. *Microb. Ecol.* 2005;49:407-415.
 79. Sudarsan JS, Roy RL, Baskar G, Deeptha VT, Nithiyantham S. Domestic wastewater treatment performance using constructed wetland. *Sust. Water Resour. Manage.* 2015;1:89-96.
 80. Tee HC, Lim PE, Seng CE, Nawi MA. Newly developed baffled subsurface-flow constructed wetland for the enhancement of nitrogen removal. *Bioresour. Technol.* 2012;104:235-242.
 81. Toet S, Van Logtestijn RS, Kampf R, Schreijer M, Verhoeven JT. The effect of hydraulic retention time on the removal of pollutants from sewage treatment plant effluent in a surface-flow wetland system. *Wetlands* 2005;5:375-391.
 82. Uggetti E, Garcia J, Lind SE, Martikainen PJ, Ferrer I. Quantification of greenhouse gas emissions from sludge treatment wetlands. *Water Res.* 2012;46:1755-1762.
 83. Vacca G, Wand H, Nikolausz M, Kusch P, Kästner M. Effect of plants and filter materials on bacteria removal in pilot-scale constructed wetlands. *Water Res.* 2005;39:1361-1373.
 84. Vymazal J, Ottová V, Balcarová J, Dousová H. Seasonal variation in fecal indicators removal in constructed wetlands with horizontal subsurface flow. *Adv. Ecol. Sci.* 2003;11:237-258.
 85. Vymazal J. Horizontal sub-surface flow and hybrid constructed wetlands systems for wastewater treatment. *Ecol. Eng.* 2005;25:478-490.
 86. Vymazal J. Plants used in constructed wetlands with horizontal subsurface flow: A review. *Hydrobiologia* 2011;674:133-156.
 87. Vymazal J. Removal of nutrients in various types of constructed

- wetlands. *Sci. Total Environ.* 2007;380:48-65.
88. Vymazal J, Greenway M, Tonderski K, Brix H, Mander U. Constructed wetlands for wastewater treatment. In: Verhoeven JTA, Beltman B, Bobbink R, Whigham DF, eds. Wetlands and natural resource management. Ecological studies. 2006. vol. 190. p. 69-96.
 89. Vymazal J, Kröpfelová L. A three-stage experimental constructed wetland for treatment of domestic sewage: First 2 years of operation. *Ecol. Eng.* 2011;37:90-98.
 90. Wiessner A, Kappelmeyer U, Kusch P, Kästner M. Sulphate reduction and the removal of carbon and ammonia in a laboratory-scale constructed wetland. *Water Res.* 2005;39:4643-4650.
 91. Wu J, Zhang J, Jia W, et al. Impact of COD/N ratio on nitrous oxide emission from microcosm wetlands and their performance in removing nitrogen from wastewater. *Bioresour. Technol.* 2009;100:2910-2917.
 92. Wu Y, Li T, Yang L. Mechanisms of removing pollutants from aqueous solutions by microorganisms and their aggregates: A review. *Bioresour. Technol.* 2012;107:10-18.
 93. Xiong J, Guo G, Mahmood Q, Yue M. Nitrogen removal from secondary effluent by using integrated constructed wetland system. *Ecol. Eng.* 2011; 37:659-662.
 94. Xu D, Xu J, Wu J, Muhammad A. Studies on the phosphorus sorption capacity of substrates used in constructed wetland systems. *Chemosphere* 2006;63:344-352.
 95. Zhou A, Wang D, Tang H. Adsorption of phosphorus on sediment-water interface. *Acta Scientiae Circumstantiae/Huanjing Kexue Xuebao* 2005;25:64-69.
 96. Yalcuk A, Ugurlu A. Comparison of horizontal and vertical constructed wetland systems for landfill leachate treatment. *Bioresour. Technol.* 2009;100:2521-2526.
 97. Zhang CB, Wang J, Liu WL, et al. Effects of plant diversity on microbial biomass and community metabolic profiles in a full-scale constructed wetland. *Ecol. Eng.* 2010;36:62-68.
 98. Zhang DQ, Jinadasa KB, Gersberg RM, Liu Y, Ng WJ, Tan SK. Application of constructed wetlands for wastewater treatment in developing countries – A review of recent developments (2000-2013). *J. Environ. Manage.* 2014;141:116-131.
 99. Zhao Y, Liu B, Zhang W, Hu C, An S. Effects of plant and influent C:N:P ratio on microbial diversity in pilot-scale constructed wetlands. *Ecol. Eng.* 2010;36:441-449.
 100. Zhu G, Wang S, Feng X, Fan G, Jetten MS, Yin C. Anammox bacterial abundance, biodiversity and activity in a constructed wetland. *Environ. Sci. Technol.* 2011;45:9951-9958.
 101. Zhuang X, Han Z, Bai Z, Zhuang G, Shim H. Progress in decontamination by halophilic microorganisms in saline wastewater and soil. *Environ. Pollut.* 2010;158:1119-1126.
 102. Garcia JA, Paredes D, Cubillos JA. Effect of plants and the combination of wetland treatment type systems on pathogen removal in tropical climate conditions. *Ecol. Eng.* 2013;58: 57-62.
 103. Tunçsiper B, Ayaz SÇ, Akça L. Coliform bacteria removal from septic wastewater in a pilot-scale combined constructed wetland system. *Environ. Eng. Manage. J.* 2012;11:1873-1879.
 104. Hill VR, Sobsey MD. Removal of Salmonella and microbial indicators in constructed wetlands treating swine wastewater. *Water Sci. Technol.* 2001;44:215-222.
 105. Hench KR, Bissonnette GK, Sexstone AJ, Coleman JG, Garbutt K, Skousen JG. Fate of physical, chemical, and microbial contaminants in domestic wastewater following treatment by small constructed wetlands. *Water Res.* 2003;37:921-927.
 106. Cirelli GL, Consoli S, Di Grande V, Milani M, Toscano A. Subsurface constructed wetlands for wastewater treatment and reuse in agriculture: Five years of experiences in Sicily, Italy. *Water Sci. Technol.* 2007;56:183-191.
 107. Gerba CP, Thurston JA, Falabi JA, Watt PM, Karpiscak MM. Optimization of artificial wetland design for removal of indicator microorganisms and pathogenic protozoa. *Water Sci. Technol.* 1999;40:363-368.